Tentative Response Analysis of
Tokai Reactor Structure due to Earthquake Ground Motion
on 3rd April, 1966

KIYOSHI MUTO *

Object In the reactor building of the Tokai Power Station, three sets of accelerometers (SMAC) were installed on the ground floor (EL 8.3m), the 5th floor (EL 33.7m) and the 6th floor (EL 40.0m). In this paper the dynamic analysis of the building was made by using the observed SMAC acceleration at the ground floor (Fig. 3(a)) as input data and the computed result was compared with the acceleration record at the Top Shield Wall.

Vibration Model System The vibration model is assumed as the coupling formation of the four systems corresponding to the reactor core, the reactor pressure vessel, the shield wall, and the surrounding building, which stand on the rigid foundation mat, as shown in Fig. 1. The foundation mat is supposed to be connected to the bedrock through the elastic intermedium, and so its rotational and swaying effect is taken into account. The calculation was made by the digital computer HITAC 5020 at the Computer Center of the Kajima Institute of Construction Technology.

Results (1) The modes and the periods of natural vibration are shown in Fig. 2.
(2) The computed time history curve of acceleration ($h = 0.2$) at the Top Shield (Point 4) is shown in Fig. 3(c) together with the SMAC record in Fig. 3(b). Comparing (b) and (c), it is found that the acceleration obtained from the analysis is larger and sharper than that of the recorded one. This suggests the necessity of the study on damping of the soil and structure.

Fig. 1 Reactor Building and Vibration Model

Fig. 3 Acceleration Curves observed and analyzed

Fig. 2 Modes and Periods of Natural Vibration

* Director, Muto Institute of Structural Mechanics